

Animal Shelter Confinement Structures - Request for Proposal

Fayette County, Tennessee is in the process of constructing an animal control facility. The anticipated date for completion/occupancy is later July to early August of 2024. It is the county's plan to purchase kennel/containment systems to be installed to maximize the animal population in the enclosed building.

All quotations must include all costs for all material, installation costs, installation documentation, shipping and coordination with the architect and construction manager. The County has considered utilizing volunteers from the county to assemble the materials, shipped to his site with appropriate detailed schematic drawings and installation documentation. For this reason, the County may or may not utilize the installation proposal and the proposal is to be offered with that option.

The proposal shall conform to the plans for the Animal Shelter, as provided at the County's website, www.fayettetn.us. As detailed on the construction documents, the system(s) to be bid will include:

1. Kennels enclosures (room 108 center section)
2. Isolation and drop off (rooms 118 and 119)
3. Cat areas (rooms 104 and 106)

The three items should be bid separately, and the County may choose at its sole discretion any one, two or three of the proposals.

Note 1: Your bid must include a detailed set of documents identifying the exact dimensions of the systems you are proposing. Refer to the construction details that exist on drain placement and floor slope to ensure proper tilt to clean out animal/waste to the sanitary waste receptacles.

Note 2: Each enclosure that abuts to another enclosure must have a partition, separator or some type of blocking screen to ensure safety and security of each animal in adjoining kennel enclosure.

Note 3: All kennel panel and door material (i.e. wire mesh) should be at least 9 ga. attached to piping of at least HF20 1 3/8" OD galvanized framing pipe and laced with a minimum non-rusting wire.

Note 4: All fittings which are used to attach panels at all joints and corners must also be treated for non-rusting.

Note 5: Latches must mount to provide a secure closure that cannot be opened by the dog.

Note 6: As noted in drawing A1.0, provide pricing for cat enclosures in room 106 and 104. These should be freestanding units and may be stackable.

The work to ship, construct, assemble and test the kennel system will be coordinated with a county representative designated prior to the issuance of deposit or purchase order.

For more information, contact the Fayette County Mayor's Office, 13095 North Main Street, Somerville, TN 38068, or email at mayor@fayettetn.us or call (901) 465-5202.

